



**CITY OF SALEM**  
**PURCHASING DEPARTMENT**

114 NORTH BROAD STREET  
P.O. BOX 869  
SALEM, VA 24153  
PHONE (540) 375-3063

**DATE: JANUARY 16, 2026**

**ITB # 2026-007**

**MISCELLANEOUS CONCRETE REPAIRS**

**DATE AND TIME PROPOSAL DUE: JANUARY 29, 2026 AT 3:00 PM (LOCAL TIME)**

**ADDENDUM # 1**

This Addendum # 1, dated January 16, 2026 amends, or supplements, Invitation To Bid (ITB) # 2026-007 as indicated below:

**I. Vendor Questions (Verbatim):**

1. Driveway (23 locations) the unit of pay/measure is listed and Linear Feet. What is the assumed width all the repaired driveway entrances? We are assuming the bid item is same as a VDOT CG-9D. Would it be possible to change to Square Feet (SF) or Square Yards (SY) on the unit of measure since the back of entrances can vary? This afford the City to have a more accurate measurement/payment of driveway entrances [sic].

Clarification by Project Manager (Verbatim): Bid the driveways as a VDOT CG 9-D width. If any driveway had a sidewalk on the backside of them that has been broken out and listed separately on the sidewalk list [sic].

2. Sidewalk (58 locations) ADA Compliant Ramps, Attachment C 447 Dalewood Ave and 204 Lewis Ave. Installation of an ADA/VDOT Compliant Ramp requires a new curb to be installed at flowline/pavement abutment; sidewalk, CG-12 ADA domes/tactile warning/ and additional curb behind the sidewalk. Would it be possible to add bid/pay items to the proposal to include CG-2 curb, CG-12 ADA domes? This would lower the overall unit price of sidewalk and allow the City to direct installation of other locations of ADA Compliant ramps [sic].

Clarification by Project Manager (Verbatim): Please bid using a standard sidewalk width of 5'.

3. Sidewalk (58 locations) ADA Compliant Ramps, Attachment C 447 Dalewood Ave and 204 Lewis Ave. Installation of an ADA/VDOT Compliant Ramp requires a new curb to be installed at

flowline/pavement abutment; sidewalk, CG-12 ADA domes/tactile warning/ and additional curb behind the sidewalk. Would it be possible to add bid/pay items to the proposal to include CG-2 curb, CG-12 ADA domes? This would lower the overall unit price of sidewalk and allow the City to direct installation of other locations of ADA Compliant ramps.

Clarification by Project Manager (Verbatim): Yes, we can add/pay items to the proposal to include GC-2 curb, CG-12 ADA domes

4. We were not able to find details/specifications for working in the City's right of way. Can we obtain specifications for items to be installed, requirements for making curb/entrance patches back against existing asphalt?

Clarification by Project Manager (Verbatim): City of Salem follows all VDOT regulations, VAMUTCD and All OSHA and VOSH regulations. Existing asphalt can be used as front edge of the form but the asphalt shall be saw cut prior to ensure the asphalt edge won't break off [sic].

**BY SIGNING THIS DOCUMENT, THE OFFEROR ACKNOWLEDGES THAT THEY HAVE RECEIVED THIS ADDENDUM # 1 AND FULLY UNDERSTANDS THESE CHANGES.**

**\*\*\*THE SIGNED ADDENDUM MUST BE INCLUDED IN THE BID SUBMITTAL\*\*\***

**OFFEROR'S SIGNATURE:**

---

**COMPANY:**

---

**END OF ADDENDUM # 1 TO ITB # 2026-007**